

TSS PLANNING FORUM HERITAGE REPORT JULY 2015

Prepared by Lynn Henstock

| TABLE OF CONTENTS | Page |
|--|-------------|
| Introduction | 2 |
| NCC Listed sites database | 3 |
| NCC Listed sites highlighted on TSS plan area | 4 |
| NCC Historic Parks and Gardens database | 5 |
| NCC Historic Parks and Gardens highlighted on TSS plan area | 6 |
| NCC Archaeological sites database | 7 |
| NCC Archaeological sites highlighted on TSS plan area | 8 |
| NCC Non-designated sites database | 9 |
| NCC Non-designated sites highlighted on TSS plan area | 10 |
| ADC local list of non-designated assets database | 11 |
| ADC local list of non-designated assets highlighted on TSS plan area | 12 |
| A brief description of the listed and non-designated assets | 13 |
| Teversal Conservation area | 17 |
| Teversal Pastures SSSI | 18 |
| Mining plan | 19 |

INTRODUCTION

Teversal, Stanton Hill and Skegby have a rich heritage and this report details the associated assets. These include all sites of interest including 'listed' assets, historic parks and gardens, archaeological assets, non-designated assets, conservation area, Sites of Special Scientific Interest (SSSI) and coal mining sites.

I have some photographs if required but have not included these in my report due to the large file size.

I contacted NCC Heritage Record Office and have received a complete record of both 'listed' assets and 'non-designated' assets registered with them. They have also sent a record of archaeological sites and historic parks and gardens. I have extracted all the sites relevant to our mapped area. ADC have also supplied a local assets list showing both locally listed and sites nominated for local listing. As a consultation exercise I contacted several groups and individuals in the area and sought their opinions and suggestions relating to the non-designated assets. I now have a list of **11 new non-designated assets** which need evaluating to identify their eligibility and relevance before they are nominated.

There are **18 NCC listed assets** – I have given a brief description of each one and have produced a database where the 18 assets have been numbered and the corresponding numbers used to identify their location on TSS plan area map. They are highlighted in red

There are **3 NCC historic parks and gardens** : – These are on a database and are numbered and are highlighted on the corresponding TSS plan area in green.

1. Skegby Hall gardens (unregistered)
2. Teversal Manor gardens (unregistered)
3. A part of Hardwick Park which lies in Teversal, Notts (registered with EH). Sir Francis Molyneux's paddock in Teversal was purchased by the Earl of Devonshire in 1664 together with the 60 fallow deer in it. (Chatsworth archives)

There are **44 NCC archaeological sites** - which I have put on a database and numbered. From the co-ordinates given on the NCC database I have been able to locate and mark these on the TSS plan area and they are highlighted in orange

Non-designated assets. *'Non-designated heritage assets are identified as having a degree of significance meriting consideration in planning decisions but which are not formally designated heritage assets.'*

The non-designated assets are in 2 parts which are:

1. **NCC registered non- designated assets (18)** These have been put on a database and numbered and are on a plan showing their location. There is also a brief history of most of the assets.
2. **ADC list of non-designated sites (47)**

This includes: a) sites which are locally listed (32)

b) sites which have been nominated for local listing (4)

c) sites which have been suggested - but have not yet been nominated for local listing (11)

These have been put on a database and numbered and are on a plan showing their location. There is also a brief history of most of the assets.

NOTTS COUNTY COUNCIL LISTED SITES DATABASE

| NOTTS COUNTY COUNCIL LISTED SITES | | | |
|-----------------------------------|--|--|------|
| <i>Coloured red on map</i> | | | |
| No.on map | Description | Guide to vicinity | Date |
| 1 | Church of St Andrew | Mansfield Road, Skegby | C13 |
| 2 | Manor farmhouse | Low Road, Skegby | C17 |
| 3 | Skegby pinfold | Mansfield Road, Skegby near Buttery Lany | C18 |
| 4 | Skegby Hall and gardens | Mansfield Road, Skegby | C18 |
| 5 | Kruck Cottage | Old Road, Skegby | C16 |
| 6 | Skegby Manor House | Mansfield Road, Skegby opp Buttery Lane | C13 |
| 7 | Stoneleigh' 215 Mansfield Road, Skegby | Mansfield Road, Skegby near Post Office | C18 |
| 8 | Church of St Katherine | Teversal village | C12 |
| 9 | The Old Rectory and adjoining garden wall | Teversal village | C17 |
| 10 | Teversal Manor | Teversal village | C16 |
| 11 | Norwood Lodge | Norwood | C18 |
| 12 | Teversal Farmhouse | Teversal village | C18 |
| 13 | The Privets | Teversal village | C18 |
| 14 | School House cottage and adjoining Manor Room | Teversal village | C18 |
| 15 | The Coach House Stable to north of the old rectory | Teversal village | C17 |
| 16 | Walled Terrace Gardens, Teversal Manor | Teversal village | C17 |
| 17 | Garages to North East of Teversal Manor | Teversal village | C17 |
| 18 | Dalestorth House | Fox and Crown crossroads | C18 |

NOTTS COUNTY COUNCIL LISTED SITES PLAN (18) – numbered in red



NOTTS COUNTY COUNCIL HISTORIC PARKS AND GARDENS DATABASE

| NOTTS COUNTY COUNCIL HISTORIC PARKS AND GARDENS SITES | | | |
|---|-------------------------------|---|-----------------------|
| <i>Coloured green on map</i> | | | |
| No.on map | Description | Guide to vicinity | Date |
| 1 | Skegby Hall gardens | adj Skegby Hall | shown OS map 1879 |
| 2 | Teversal manor gardens | adj Teversal Manor | Sanderson map 1835 |
| 3 | Hardwick park - EH registered | adj Hardwick Hall in NW part of Teversal - on Notts/Derbys border | land transferred 1664 |
| | | | |

NOTTS COUNTY COUNCIL HISTORIC PARKS AND GARDENS PLAN (3) - numbered in green



NOTTS COUNTY COUNCIL ARCHAEOLOGICAL SITES DATABASE

| NOTTS COUNTY COUNCIL ARCHAEOLOGICAL SITES | | | | | | |
|---|--------------------------------------|--|------------------|------------------------|------------|------------|
| <i>Coloured orange on map</i> | | | | | | |
| No.on map | Description | Guide to vicinity | Date | Classification | Grid ref E | Grid ref N |
| 1 | Skegby Mill | car boot site | Medieval-modern | Watermill | 449500 | 360950 |
| 2 | Skegby Manor <i>farm</i> | adj Pond cottage | from 1207 | Manor house | 449600 | 360910 |
| 3 | Medieval bloomery near Skegby church | behind stone wall south of St Andrews church | medieval | Bloomery | 449300 | 360900 |
| 4 | Kiln site in WE1 | Hardwick Park farm area | U | Pottery kiln | 447230 | 363920 |
| 5 | Flint working site in RLN1 | NW of trail off Newnoundmill lane | prehistoric | Lithic working site | 449200 | 363400 |
| 6 | Deserted medieval village | SSE of Springwood Farm Stanton hill | medieval | Deserted village | 447900 | 360400 |
| 7 | Church of St Andrew | Skegby | medieval | Church | 449250 | 360970 |
| 8 | Church of St Katherine | Teversal | from C12 | Church | 448340 | 361900 |
| 9 | Elizabethan (aka Kruck) cottage | Old Road Skegby | c.1613 | Timber framed house | 449750 | 361000 |
| 10 | Victorian baths | Teversal | P medieval - mod | baths | 448310 | 361650 |
| 11 | Quarry | Hucklecroft, Teversal | U | Quarry | 448250 | 362450 |
| 12 | Fish pond N of Ladywell, Teversal | North east of Teversal village | U | Fishponds | 448790 | 362370 |
| 13 | Fish ponds, Skegby Hall | Skegby Hall | P medieval | Fishponds (ornamental) | 449370 | 360790 |
| 14 | Newbound Mill, Teversal | Newboundmill | medieval, P med | Watermill | 449453 | 363243 |
| 15 | Ford near Newbound Mill | Newboundmill | U | Ford | 449460 | 363240 |
| 16 | Limestone quarries, Skegby | West of Skegby church | U - mod | Limestone quarry | 449100 | 361000 |
| 17 | Sewage works, Skegby | West of Healdswood | by 1917 | Sewage works | 448400 | 361120 |
| 18 | Old quarry, Skegby | Back Lane, Skegby | pre 1918 | Limestone quarry | 449900 | 360990 |
| 19 | Spring Wood Cottages | field to west of Stanton Hill | by 1918 | House | 447380 | 360560 |
| 20 | Smithy | opp Carnarvon Arms | by 1918 | blacksmiths workshop | 447500 | 361420 |
| 21 | Brickworks | off Chesterfield Road, Whiteborough | C19 | Brickworks | 445850 | 360930 |
| 22 | Coal mine, SE of fackley farm | off Fackley Road, Teversal | pre 1918 | Coal mine | 447740 | 361150 |
| 23 | Boundary stones | Dovedale Wood, Hardwick park area | U - mod | Boundary stone | 446600 | 363300 |
| 24 | Silverhill colliery | off Silverhill Lane, Teversal | by 1879 | Colliery | 447160 | 361660 |
| 25 | Limestone quarry | off Chesterfield Road, Whiteborough | U | Limestone quarry | 445630 | 360690 |
| 26 | Dunsill house | off Silverhill Lane, Teversal | P med - mod | House | 446830 | 361920 |
| 27 | Windpump | North east of Teversal village | by 1917 | Windpump | 448900 | 362380 |
| 28 | Coal mine | field to west of Stanton Hill | pre 1918 | Coal mine | 446700 | 360460 |
| 29 | Coal mine | field to west of Stanton Hill | pre 1918 | Coal mine | 446900 | 360450 |
| 30 | Tramway | off Wharf Road, west of Stanton Hill | C19 | Tramway | 448100 | 360700 |
| 31 | Trackway | field to west of Stanton Hill | pre 1918 | Trackway | 447310 | 360430 |
| 32 | Coal mine | field to west of Stanton Hill | pre 1918 | Coal mine | 447400 | 360440 |
| 33 | Coal mine | field to west of Stanton Hill | pre 1918 | Coal mine | 447580 | 360650 |
| 34 | Coal mine | field to west of Stanton Hill | pre 1918 | Coal mine | 447940 | 360690 |
| 35 | Molyneux colliery | off Fackley Road, Teversal | pre 1918 | Colliery | 447840 | 360950 |
| 36 | Coal mine | off Wharf Road, west of Stanton Hill | pre 1918 | Coal mine | 448070 | 360770 |
| 37 | Skegby Old Wharf | off Wharf Road, west of Stanton Hill | pre 1918 | Coal depot | 448100 | 360680 |
| 38 | Limestone quarry | opp. Maypole PH, Skegby | pre 1918 | Limestone quarry | 450100 | 361160 |
| 39 | Limestone quarry and lime kilns | opp. Maypole PH, Skegby | by 1918 | Lime kiln | 450080 | 361220 |
| 40 | Quarry | opp. Maypole PH, Skegby | U | Limestone quarry | 449980 | 361120 |
| 41 | Possible building in WE3 | Hardwick Park area | U | Building | 447230 | 363360 |
| 42 | Lime kilns | west of Skegby church | P med - mod | Lime kiln (quarry) | 449100 | 361000 |
| 43 | Sutton Grange House | off Cosgrove Ave/Dalestorth Road | late med - 1993 | Building (Grange) | 450570 | 360160 |
| 44 | Mid C12 pottery kiln, Skegby | rear of 116 Mansfield Road, Skegby | Mid C12 | Pottery kiln | 449200 | 360800 |

NOTTS COUNTY COUNCIL ARCHAEOLOGICAL SITES PLAN (44) – numbered in orange



NOTTS COUNTY COUNCIL NON-DESIGNATED ASSETS DATABASE

| NOTTS COUNTY COUNCIL NON-DESIGNATED SITES | | | |
|---|---|---------------------------------|-----------|
| <i>Coloured yellow on map</i> | | | |
| No.on map | Description | Guide to vicinity | Date |
| 1 | Skegby and Stanton Hill branch library | Mansfield Road, Healdswood | C20 |
| 2 | Headstone dated 1631, St Katherine's churchyard | St Katherine's churchyard | C17 |
| 3 | Lime tree cottage | Buttery Lane, Teversal | C19 |
| 4 | Manor Cottage | Pleasley Road, Teversal village | C18 |
| 5 | One Ash and adjoining Ashfield Cottage | Buttery Lane, Teversal | |
| 6 | 1 & 2 The Elms | Pleasley Road, Teversal village | |
| 7 | Hillcroft farmhouse | Pleasley Road, Teversal village | |
| 8 | Grange bungalow | Pleasley Road, Teversal village | |
| 9 | Teversal County Primary School | Pleasley Road, Teversal village | |
| 10 | Greystones Terraces | Buttery Lane, Teversal | |
| 11 | Manor farmhouse | Buttery Lane, Teversal | |
| 12 | The Grange | Pleasley Road, Teversal village | |
| 13 | Newboundmill farm | Newboundmill Lane Teversal | Sanderson |
| 14 | City of Whiteborough farm | off Wild Hill, Teversal | Chapman |
| 15 | Newbound farm | Newboundmill Lane Teversal | Sanderson |
| 16 | Penniment house farm | Penniment Lane, Skegby | Chapman |
| 17 | Silverhill farm | off Wild Hill, Teversal | Sanderson |
| 18 | Buildings adjacent Teversal Manor | near Teversal Manor | C19 |


NOTTS COUNTY COUNCIL NON-DESIGNATED ASSETS PLAN (18) – numbered in dark yellow



ADC LOCAL LIST OF NON-DESIGNATED ASSETS DATABASE

| ADC LOCAL LIST OF NON-DESIGNATED ASSETS | | | | | | |
|---|--------------------------------------|---|--------------|-------------------|---------|----------|
| <i>Coloured blue on map</i> | | | | | | |
| No.on map | Description | Guide to vicinity | | Status | Easting | Northing |
| 1 | Baths | South of Teversal Manor, Teversal | Teversal | Locally Listed | 448310 | 361650 |
| 2 | Fishponds, Skegby Hall | Mansfield Road, Skegby | Skegby | Locally Listed | 449370 | 360790 |
| 3 | Newbound Mill | Newbound Mill Lane, Teversal | Teversal | Locally Listed | 449453 | 363243 |
| 4 | Dunsill House | Silverhill Lane, Teversal | Teversal | Locally Listed | 446830 | 361920 |
| 5 | Quaker House | 113 Mansfield Road, Skegby | Skegby | Locally Listed | 449440 | 360980 |
| 6 | Penniment House Farm | Penniment Lane, Skegby/Mansfield border | Mansfield | Locally Listed | 450835 | 362027 |
| 7 | City of Whiteborough Farm | Wild Hill, Teversal | Teversal | Locally Listed | 446604 | 360766 |
| 8 | Wesleyan Chapel | Mansfield Road, Skegby | Skegby | Locally Listed | 449843 | 360914 |
| 9 | Silverhill Farm; Silver Hill | Wild Hill, Teversal | Teversal | Locally Listed | 446923 | 361311 |
| 10 | Colliery Houses | Co-operative street, Stanton Hill | Stanton Hill | Locally Listed | 448339 | 360623 |
| 11 | Workmens Club | Institute Street, Stanton Hill | Stanton Hill | Locally Listed | 448459 | 360590 |
| 12 | The Terraces | Off Stoneyford Road, Stanton Hill | Stanton Hill | Locally Listed | 448630 | 360600 |
| 13 | Primitive Methodist Chapel | 66 Longdon Terrace (New Lane), Stanton Hill | Stanton Hill | Locally Listed | 448566 | 360662 |
| 14 | General Baptist Church | Albert Street, Stanton Hill | Stanton Hill | Locally Listed | 448488 | 360670 |
| 15 | 9 High Street | 9 High Street, Stanton Hill | Stanton Hill | Locally Listed | 448388 | 360673 |
| 16 | Carnarvon Arms Public House | Fackley Road, Teversal | Teversal | Locally Listed | 447516 | 361396 |
| 17 | Hall's Yard | 276 Mansfield Road | Skegby | Locally Listed | 450126 | 360647 |
| 18 | Hall's Yard | 278 Mansfield Road | Skegby | Locally Listed | 450138 | 360640 |
| 19 | All Saints Church | Fackley Road, Stanton Hill | Stanton Hill | Locally Listed | 448493 | 360803 |
| 20 | Breather Pole | Low Road, Skegby | Skegby | Locally Listed | 449931 | 361089 |
| 21 | The Dovecote | Old Road, Skegby | Skegby | Locally Listed | 449740 | 361012 |
| 22 | Stanley House Farm | Stanley Lane, Stanley | Teversal | Locally Listed | 446115 | 362327 |
| 23 | Dame School | Fackley Road, Teversal | Teversal | Locally Listed | 447574 | 361369 |
| 24 | Silverhill Cottages | Silverhill Lane, Teversal | Teversal | Locally Listed | 447276 | 361545 |
| 25 | St Andrews School | Mansfield Road, Skegby | Skegby | Locally Listed | 449807 | 360840 |
| 26 | Station House - Midland railway | Fackley Road, Teversal | Teversal | Locally Listed | 447677 | 361311 |
| 27 | Burrow's butchers' house | 151 Mansfield Road, Skegby | Skegby | Locally Listed | 449802 | 360960 |
| 28 | Whiteboro Cottage | Wild Hill, Teversal | Teversal | Locally Listed | 445768 | 360961 |
| 29 | Wild House - GN stationmasters house | Pleasley Road, Teversal | Teversal | Locally Listed | 447785 | 361603 |
| 30 | Fackley Farm | Fackley Road, Teversal | Teversal | Locally Listed | 447616 | 361245 |
| 31 | Telephone Box | Buttery Lane, Teversal village | Teversal | Locally Listed | 448146 | 361858 |
| 32 | Dawgates Lane (Roman trackway) | Dawgates Lane, Skegby | Skegby | Locally Listed | 0 | 0 |
| 33 | Stables | High Street, Stanton Hill | Stanton Hill | Nominated Site | 448472 | 360636 |
| 34 | Howlish | Pleasley Road, Teversal | Teversal | Nominated Site | 447750 | 361676 |
| 35 | Hucklecroft | Pleasley Road, Teversal | Teversal | Nominated Site | 448254 | 362415 |
| 36 | Yew Tree Cottage | Pleasley Road, Teversal | Teversal | Nominated Site | 448257 | 362423 |
| 37 | Skegby troughs | Old Road, Skegby | Skegby | Not yet nominated | 449769 | 360989 |
| 38 | Rifle Volunteer PH | Forest Road, Skegby | Skegby | Not yet nominated | 449993 | 360484 |
| 39 | White cottage adj Rifle Volunteer | Forest Road, Skegby | Skegby | Not yet nominated | 450002 | 360481 |
| 40 | Park House | Forest Road, Skegby | Skegby | Not yet nominated | 449875 | 360522 |
| 41 | Kelham Cottages | Mansfield Road, Skegby | Skegby | Not yet nominated | 450160 | 360625 |
| 42 | The Maypole PH | Dawgates Lane, Skegby | Skegby | Not yet nominated | 449944 | 361093 |
| 43 | Church Farm | Mansfield Road, Skegby | Skegby | Not yet nominated | 449662 | 361024 |
| 44 | Skegby GN station House | Buttery Lane, Skegby | Skegby | Not yet nominated | 449553 | 361116 |
| 45 | Orchard farm Cottages | Wild Hill, Teversal | Teversal | Not yet nominated | 447008 | 360981 |
| 46 | Miners statue, Silverhill Woods | Silverhill Woods, Teversal | Teversal | Not yet nominated | 447067 | 362125 |
| 47 | Hamlet of Stanley | Stanley, Teversal | Teversal | Not yet nominated | 446109 | 362238 |

ADC LOCAL LIST OF NON-DESIGNATED ASSETS PLAN (47) -numbered in blue



A BRIEF DESCRIPTION OF LISTED AND NON-DESIGNATED ASSETS

This list includes a brief description of all listed assets within the TSS plan area and many, but not all, of the non-designated assets.

LISTED ASSETS IN TEVERSALE, STANTON HILL AND SKEGBY (18)

Manor Farmhouse, Low Road, Skegby. Manor farm was built in the 17th century as the farmhouse for Skegby manor.

Kruck Cottage Kruck cottage dates from at least the 16th century and is the oldest occupied domestic dwelling remaining in Skegby

St Andrews Church St Andrews Church in its current form dates from 1870 but has many Norman connections and dates from at least this period

Skegby Pinfold Skegby Pinfold was used to contain stray animals pending contact with their rightful owners and payment of a fine. It dates from the 18th century.

Skegby Hall and Gardens Skegby Hall and Gardens were built around 1720 by the Lindley family on the foundations of a much earlier dwelling. The hall has been in continuous occupation.

Skegby Manor House Skegby Manor House dates from the early 13th century and has seen many changes and uses since that date

Dalestorth House The main house is 18 C and was enlarged about 1770. The stone portion to the east is formerly part of the 'Old Cock Inn' (1600 – 1750). In White's directory 1832 it is described as a Ladies Boarding Establishment. For an annual fee of 20 guineas young women could receive instruction on needlework, reading, writing, composition arithmetic and grammar.

Stoneleigh, 215 Mansfield Road Skegby Late C18 house with late C19 alterations

Teversal farmhouse, Buttery lane The two storey building dates from the late 18th Century and is constructed of coursed and squared rubble with a bright red pan tiled roof and stone slab verges. The windows are mainly 19th Century casements and glazing bar sashes with projecting architraves.

The Privets, Buttery Lane 18th Century Grade II Listed cottage. The cottage is rendered with dark red, gabled and lean to pan-tile roofs and ashlar stone dressings.

School House Cottage and adjacent Manor Room, Buttery Lane Originally the property may have been a tithe barn, with a thatch or stone roof. In the 19th century it was converted to a school, with additions in the mid and late 19th Century. School house cottage was where the first school was located and became the home of the schoolmistress when the school moved next door to what is now the Manor Room The building was affected during the past 50 years due to mining subsistence although this has been rectified by the recent refurbishment programme which was completed in 2006.

Church of St Katherine, Buttery lane The oldest building in Teversal village is St Katherine's Church. Originally a wooden structure, the current structure is the only Grade I listed building in the settlement and originally dates from the 12th and 13th Centuries although it was fenestrated and refitted around 1684. The original structure of the building is constructed of coursed and squared rubble with lead and slate lean-to and gabled roofs. This is supplemented with Ashlar dressings, coved eaves, and coped gables with kneelers and crosses.

The Coach House – Stable North of the Old rectory, Buttery Lane This property once belonged to the Old Rectory. The dwelling is constructed of coursed and square Rubble and contains modern casement windows and skylights.

The Old Rectory and adjacent garden wall, Buttery Lane The Old Rectory and the high garden wall which adjoins it are Grade II listed and date from around the late 17th Century, the entry possessing an impressive set of tall gate piers. The property was refenestrated and additions to the building were added in the mid 19th Century. The building is constructed of coursed and squared rubble, partly rendered, with slate roofs and possesses mainly 19th Century sash windows with cornices.

Norwood Lodge, Newbound Lane This was once a farmhouse and is now a house. Dated 1738 with early C19 additions. To the south front is a central round headed window and over it a datestone inscribed 'NTA 1738'. Cellar contains salting trough and benches. This building was restored from a derelict state in 1985.

Teversal Manor Buttery Lane The Grade II listed Manor has wooden gates which bear the Molyneux family cross. The main building is constructed from coursed and dressed rubble stone with ashlar dressing. In the gable is a small square plaque containing a shield and the date 1764 which indicates that this is one of the oldest sections of the building. The western section of the building dates from 1896. The eastern wing of the house is the oldest in the Manor having a single 17th Century 3 light mullion window on the upper floor.

Garages to north East of Teversal Manor, Buttery Lane A Grade II Listed Building (Garages to the North East of Teversal Manor), known locally as the Gate House, is situated to the side of Teversal Manor. This building has been sensitively restored and converted into a dwelling.

Walled Terrace gardens with steps and gatepiers south of Teversal Manor 3 walled terrace gardens. Late C17 the walls are roughly 2 metres high around 3 rectangular terraced gardens. The upper terrace has 2 small flights of steps at each corner and on the south side a large flight of steps leading down to the lower terrace. A similar central flight of steps leads down to the bottom terrace, which has a central set of square gatepiers with moulded caps and ball finials supported on ogee bases.

NON-DESIGNATED HERITAGE ASSETS IN TEVERSAL, STANTON HILL AND SKEGBY

SKEGBY

Skegby Troughs Skegby troughs are ancient spring fed animal watering troughs thought to have been used by travellers on the toll road that started where Old Road now joins Mansfield Road

St Andrews School St Andrews School was built in 1865 on land donated by Lady Carnarvon.

The Quaker House The Quaker House was the home of Elizabeth Hooton, one of the founders of the Quaker movement in England. The house was built in the 17th century.

Kelham cottages Kelham cottages were former stables and are thought to be 18th century

Hall's yard – A pair of stone-built cottages divided by an arched carriage way and probably dating from the 18th century. The property was once inhabited by the Hall family after whom the yard was named.

The Rifle Volunteer PH – A building is shown on this site on Sanderson 1835 map and tithe plan

The Maypole PH – Built in the early 20th century and previously called the White Swan the building stands on the site of an earlier public house

Station House (Skegby) The Great Northern stationmasters house was built in 1897.

Park House This was once the home of the late local historian Bill Clay-Dove and is thought to have been built in the 18th century

Dawgates Lane A Neolithic trackway which in Roman times linked Broxtowe fort, Nottingham to Templeborough fort, Rotherham

STANTON HILL

Cottage on High Street -with adjoining Victorian buildings on either side. This is said to be the earliest building on Stanton Hill but is not shown on either the Chapman 1774 or Sanderson 1835 map.

Band Hall – Institute Street In 1875 one hundred and thirty two houses were built on **Institute Street** and **Co-operative street** for the workmen at the new collieries at Teversal and one was converted into an Institute and Recreation centre.

Methodist chapel – New Lane The Primitive Methodist chapel was built on New Lane in 1876 and used until 1908 when a new chapel was built on Albert Street. The old chapel is currently used as a car repair garage

Baptist Church - Albert Street The foundation stone of the Baptist church bears a date of 1877. This church is still in use.

All Saints Church – Fackley Road The foundation stone was laid by the Dowager Countess of Carnarvon in 1899 and the church was opened in 1900.

TEVERSAL (OLD VILLAGE) CONSERVATION AREA

Telephone box - A traditional style red telephone box in local ownership

WIDER TEVERSAL AREA INCLUDING HAMLETS

Carnarvon Arms public house The Carnarvon Arms PH stands on the crossroads at Fackley and was originally called the Cross Keys before becoming the Carnarvon Arms in 1870. The mid section of the west wing is thought to be early to mid 18th century and original beams are still visible. An extension to this wing was made in 1793.

Midland railway stationmasters house - Fackley Road Built in 1885 by J Slaters together with the platform and station. This station was renamed Teversal Manor station in 1950 to differentiate between this and the Great Northern station.

Great Northern railway stationmasters house - Pleasley Road A large and elegant red brick building. It was built in 1897 together with a small goods yard with one siding and a weighbridge. This station was renamed Teversal East station in 1950 to differentiate between this and the Midland railway station.

Silverhill Cottages These were known as 'sinkers' cottages and were built for the workers who sank Teversal and Silverhill pits. They were built in the mid-late 19th century.

Silverhill Farm The present building was built in 1865 and replaced an earlier building. Lady Carnarvon stayed here whilst renovations were made to Teversal Manor in the 1890's.

Howlish House This property has the distinctive Carnarvon cross and was built late C19

City of Whiteborough Farm Buildings are shown on this site on Chapman 1774, Sanderson 1835 and 1841 tithe maps

Newbound Mill Farm The farmhouse adjacent to the mill is shown on Sanderson map 1835 and 1841 tithe plan and is believed to date from Elizabethan times

Orchard farm cottages The cottages are attached to the current farmhouse but are much earlier. They are stone built and are shown on both Chapman 1774, Sanderson 1835 and 1841 tithe maps and are probably 18th century.


'Testing for gas' statue Commemorative statue on former Silverhill colliery spoil heap

The hamlet of Stanley The hamlet of Stanley as a whole should be included as a non-designated heritage asset. There are a number of old farms and barns of varying ages – most of which are now residential properties – which have been renovated in keeping with their surroundings. Whilst most properties have retained some original features there have been some modern additions made. The hamlet has a rural setting and a rich heritage dating from the C12 which should be preserved. Teversal heritage group are currently investigating Stanley - though research is incomplete at this date.

Teversal Conservation Area appraisal - should be included in full.

Map: http://www.ashfield-dc.gov.uk/media/454900/teversal_conservation_area.pdf

Appraisal: http://www.ashfield-dc.gov.uk/media/454897/teversal_conservation_area_appraisal.pdf



Teversal Pastures SSSI Site of Special Scientific interest – this should be noted.

<http://www.ashfield-dc.gov.uk/residents/planning,-property-and-housing/forward-planning/environment-and-conservation/sites-of-special-scientific-interest.aspx>



Mining in the Meden Valley

Plan showing the Skegby (Meden Valley) pits drawn by Robert Bradley – mining surveyor and historian.

